



# NEWPORT

KENTUCKY

## Memo

**To:** All interested parties  
**From:** Larisa Sims, Assistant City Manager  
**Date:** 5/29/2019  
**RE:** Addendum #2 - "6-434 Newport Riverfront Commons"

---

The following additional information and addendums are the result of inquiries from 5/21/2019 – 5-29-2019

1. Question: Page S-100 and S-300 show piling being driven on a batter. The existing bridge is too close to lean the leads for the pile driving. Can these piles be driven vertical or maybe less batter. Please clarify.
  - a. Answer: 12" diameter auger cast piling can be used in lieu of driven 12" CIP piles. The batter can be reduced to 1:6 (9.5 degrees) from the original 1:4 as well.
2. Follow Up Question: 12" diameter auger cast piling can be used in lieu of driven 12" CIP piles. What would be the length of the auger cast be and would any testing be required.
  - a. Answer: 12" diameter auger cast piling can be used in lieu of driven 12" CIP piles. The batter can be reduced to 1:6 (9.5 degrees) from the original 1:4 as well. The pile lengths will be the same for each option.